



CTI Engineers, Inc.  
1122 Riverfront Parkway  
Chattanooga, TN 37402  
Phone 423.267.7613  
Fax 423.267.0603  
www.ctiengr.com

TO: W & O Construction Brandy Garrett [bids@wocc.com](mailto:bids@wocc.com)  
 Haren Construction Company, Inc. Cynthia Osborne [cosborne@harenconstruction.com](mailto:cosborne@harenconstruction.com)  
 Judy Construction Company, Inc. Owen Yocum [owen@judyconstructionco.com](mailto:owen@judyconstructionco.com)  
 J. Cumby Construction, Inc. Greg Shirley [gshirley@jcumbyconstruction.com](mailto:gshirley@jcumbyconstruction.com)  
 Southern Constructors, Inc. Mike Huenefeld [mhuenefeld@southerconstructorsinc.com](mailto:mhuenefeld@southerconstructorsinc.com)  
 Norris Bros Excavating, LLC Jacob Norris [norrisbrosexcavating@hotmail.com](mailto:norrisbrosexcavating@hotmail.com)  
 Conti Corporation Danny Page [dpage@conticorporation.com](mailto:dpage@conticorporation.com)

City of Cookeville Barry Turner [bturner@cookeville-tn.gov](mailto:bturner@cookeville-tn.gov)  
 Associated General Contractors Cathy Stone [cathy@agcetn.org](mailto:cathy@agcetn.org)  
 Builders Exchange of Tennessee [reporter@bxtn.org](mailto:reporter@bxtn.org)  
 CMD Planroom [docprocessing@cmdgroup.com](mailto:docprocessing@cmdgroup.com)  
 Dodge Data & Analytics [dodge.docs@construction.com](mailto:dodge.docs@construction.com)

FROM: John King, P.E., Senior Project Manager

DATE: March 23, 2020

PROJ. NO.: K19001-02

SUBJECT: Addendum No. 3  
City of Cookeville, TN  
Wastewater Treatment Plant Solids Handling Improvements

PAGES: 2 pages follow

<p><b>PLEASE RESPOND</b></p> <p>→ → → →</p>	<p><b>TO CONFIRM RECEIPT OF THIS ADDENDUM NO. 3</b></p> <p><b>PLEASE SIGN AND EMAIL TO CTI</b></p> <p><a href="mailto:igonzalez@ctiengr.com">igonzalez@ctiengr.com</a></p>
	<p>Company _____</p>
	<p>Signature _____</p>
	<p>Title _____</p> <p>Date _____</p>

## ADDENDUM NO. 3

### CONTRACT DOCUMENTS, SPECIFICATIONS, AND DRAWINGS FOR THE COOKEVILLE WWTP SOLIDS HANDLING IMPROVEMENTS

The following changes shall be made to the Contract Documents, Specifications, and Drawings:

#### I. CONTRACT DOCUMENTS

##### A. *Section 00 42 00 - Bid Schedule*

1. Page 00 42 00- 3.2. On the equipment supplier selection under Section 41 21 14, Shaftless Screw Conveyors, ADD a line for KWS in addition to Spirac and Jim Myers (JMS).

#### II. SPECIFICATIONS

##### A. *Section 01 11 00 – Summary of Work*

1. Page 01 11 00-2. ADD the following subparagraph to Paragraph 1.1.C:  
  
“7. Oxidation Ditches  
a. Add scum baffle to weir box on Oxidation Ditch No.1 and No. 2.”
2. Page 01 11 00-5. ADD the following paragraph to Paragraph 1.8.I, as previously amended by Addenda Nos. 1 and 2:  
  
“Dewatered sludge may be transported to Upper Cumberland Solid Waste Landfill (931-258-3954) located at 776 Terry Odle Road in Red Boling Springs, TN. The Contractor may self-transport the sludge, or may use a hauling contractor such as TDS Disposal (800-968-3954), also located in Red Boling Springs.”
3. Page 01 11 00-5. ADD the following paragraph to Section 1.8, as previously amended by Addendum Nos. 1:  
  
“M. For installation of the new scum baffles on the weir boxes of Oxidation Ditch Nos. 1 and 2, the water level in a ditch may be lowered for 6 to 8 hours per day for demolition of the old scum baffle and installation of the new scum baffle. A ditch can operate several days without the old scum baffle.”

##### B. *Section 01 29 76 – Applications for Payment*

1. Page 01 29 76-2. ADD the following paragraph to Section 1.8:  
  
“F. Notwithstanding the above, the Contractor may submit an application for payment immediately following issuance of the Notice to Proceed covering the customary bonds and insurance plus any initial payment for lime treatment equipment that must be paid concurrent with the order (not to exceed 10 percent of the cost of the lime treatment equipment).”

**C. Section 11 33 00 - In-Line Sewage Grinder**

1. Page 11 33 00-3. ADD the following sentence to Paragraph 2.2.A:

“Although the specification is written around the JWC Muffin Monster, the design of Franklin Miller is acceptable where it differs from that specified for the JWC Muffin Monster, insofar as it is otherwise not possible to meet the requirements of the specification as written.”

**III. DRAWINGS**

**A. Drawing No. 27.0 – Lime Treatment Building Floor Plan, Sections, and Pushwall Details**

1. ADD the following note next to the existing electrical room on the building floor plan:

**NOTE:**

Expand the existing metal building in the direction of the doorway by an additional 4 feet. Match existing metal building. Retain and reuse existing double door and frame.”

Date: March 23, 2020

CTI Engineers, Inc.  
/s/ Gary M. Cosby, P.E.  
Senior Project Manager