



CTI Engineers, Inc.
 1122 Riverfront Parkway
 Chattanooga, TN 37402
 Phone 423.267.7613
 Fax 423.267.0603
 www.ctiengr.com

LETTER OF TRANSMITTAL

TO: Northwest Georgia Paving, Inc. tprice@nwgpinc.com
 Integrated Properties, LLC ssewart@integratedbuilds.com
 C&G Concrete Construction cag@cagconcrete.com
 Talley Construction, Inc. tfountain@talleyconstruction.net

The Blue Book emcveigh@mail.thebluebook.com
 Dodge Data & Analytics dodge.bidding@construction.com
 Builders Exchange of Tennessee heather@bxtn.org
 Associated General Contractors planroom@agcetn.org
 ConstructConnect amelia.mcmahan@constructionconnect.com

Dan Wright danwright@cityofringgoldga.gov
 Mike Cagle pw@cityofringgoldga.gov
 Nicki Lundeen nickilundeen@cityofringgoldga.gov

FROM: Philip Schofield, P.E.

DATE: August 26, 2020

PROJ. NO.: G14028

SUBJECT: Addendum No. 2
 City of Ringgold
 Boynton Drive Sidewalk

PAGES:
 10 pages to follow

<p>PLEASE RESPOND</p> <p>➔ ➔ ➔ ➔</p>	<p>TO CONFIRM RECEIPT OF THIS ADDENDUM NO. 2 PLEASE SIGN AND EMAIL TO CTI</p> <p>vvisco@ctiengr.com</p>
	Company _____
	Signature _____
	Title _____
Date _____	

647418

**ADDENDUM NO. 2
CITY OF RINGGOLD, GEORGIA
BOYNTON DRIVE SIDEWALKS**

The following changes shall be made to the Contract Documents and Specifications

I. CLARIFICATIONS

- A. All lighting and associated electrical work will be performed by the City of Ringgold. The Contractor shall coordinate with the City in select locations regarding placement of conduit that crosses under the new sidewalk.

II. CONTRACT DOCUMENTS

- A. **Section 00 42 00, Bid Schedule:** DELETE Pages 00 42 00-1.1 through 00 42 00-9.1 and SUBSTITUTE therefor the attached pages 00 42 00-1.2 through 00 42 00-9.2.

August 26, 2020

CTI ENGINEERS, INC.
/s/Philip Schofield, P.E.
Project Manager

**BID SCHEDULE FOR UNIT PRICE
BOYNTON DRIVE SIDEWALKS
RINGGOLD, GEORGIA**

Note: Unless otherwise stated, all bid items shall be a complete installation as specified and/or shown on the Drawings.

Item No.	Description	Unit	Est. No. of Units	Unit Price	Item Total
SCHEDULE I - STATION 39+45 TO STATION 33+00 (DRAWING NO. 11.2)					
01 22 00	Mobilization and Performance Bond (Max 4.5% of Bid), Including Elevation Control, Site Layout, Utility Location, and Construction Staking	LS	1		
01 22 00b	Traffic Control Devices to Meet MUTCD and GDOT Requirements	LS	1		
03 30 00	Cast-In-Place Concrete, Includes All Materials and Labor				
03 30 00a	Class B (3,000 psi) Concrete for Utility Crossings , Including Excavation, Bedding, and Backfill in Areas Shown on the Plans and as directed by the Engineer	CY	5		
03 30 00b	Class A (4,000 psi) Concrete for Culvert Crossing Structure , Shown on Drawing 11, Including Excavation, Bedding, Form Work, Steel Reinforcement, Grouting, Finish Rubbing, Handrail Installation, and Site Restoration, Complete In Place as Shown in Detail on the Plans and as directed by the Engineer	LS	1		
03 30 00c	Class A (4,000 psi) Concrete for Junction Structure , Shown on Drawing 11, Including Excavation, Bedding, Form Work, Steel Reinforcement, Grouting, Finish Rubbing, and Site Restoration, Complete in Place as Shown in Detail on the Plans and as directed by the Engineer	LS	1		
03 30 40	Concrete Sidewalks and Driveways, Includes All Materials and Labor				
03 30 40a	4-Inch-Thick Concrete for Sidewalk , Class A (4,000 psi), Including Excavation, Grading, Subgrade Preparation with up to 4-inches of Base Stone, Concrete Poured and Finished, Ramps, Joints, etc., Complete-in-Place	LF	350		
03 30 40b	Concrete Sidewalk with Turned Down Header Curb (Less than 30" Tall) at Front or Back of Sidewalk , Class A (4,000 psi), Including Saw Cutting, Excavation, Form Work, Pouring and Finishing Concrete Curb, Expansion Joints, Caulking, and Parking Lot Repair, Complete in Place	LF	300		
03 30 50	Concrete Curb, Concrete Gutter, or Combined Curb and Gutter				
03 30 50a	Concrete Header Curb , Class A (4,000 psi), Including Saw Cutting, Excavation, Stone Bedding, Form Work, Pouring and Finishing Concrete Curb, Expansion Joints, Caulking, and Roadway Repair, Complete in Place	LF	10		
03 30 50b	Concrete Curb and Gutter , Class A (4,000 psi), Including Saw Cutting, Excavation, Form Work, Pouring and Finishing Concrete, Expansion Joints, Caulking, and Asphalt Repair, Complete in Place	LF	40		
	Signage				
636-1	Remove and Relocate Stop Sign, Warning Sign, or Street Sign	EA	1		

Item No.	Description	Unit	Est. No. of Units	Unit Price	Item Total
31 20 00	Earthwork				
31 20 00a	Unclassified Demolition/Excavation. Unclassified Demolition/Excavation of Existing Roadway, Curbs, Sidewalks, Brick and Debris Required to Fully Prepare the Sidewalk Subgrade; Including Saw-Cutting, Removal and Disposal of Spoil, Cuts and Fills Where Necessary, Ditch Grading, and Re-Setting Valve Covers, and Meter Boxes	LS	1		
31 20 00b	Crushed Rock Bedding Material in Excess of Standard Bedding or Leveling, Not Paid in Concrete Items Where Unsuitable Soil is Encountered or Where Additional Material for Bedding or Grading is Required or as Directed by the Engineer, Including Undercut Excavation, Disposal, and Stone Placement	TN	20		
31 25 00	Slope Protection and Erosion Control				
31 25 00a	Compost Filter Sock, Including Installation of Posts and Removal After Site Stability	LF	200		
31 25 00b	Rip Rap Stone, Complete-in-Place Where Shown on Plans for Ditch Construction, Outlet Protection, Slope Protection, Check Dams, and as Directed by the Engineer. Including Excavation, Filter Fabric Installation and Stone Placement, Complete in Place	TN	120		
31 25 00c	Straw Matting for Slope or Ditch Stabilization, Including Staples, as Shown on the Plans or as directed by the Engineer or Owner	SY	800		
31 25 00d	Concrete Washout Structure	EA	1		
32 10 00	Paving and Striping				
32 10 00a	Thermoplastic Cross Walk Striping, Including 5-Inch White Traffic Stripe per GDOT Standard T-11A, Complete in Place, Paid by Linear Foot Station to Station Across Drives and Roads	LF	85		
32 10 00b	Thermoplastic Solid Stripe for Stop Bar, Including 24-Inch White Traffic Stripe per GDOT Standard, Complete in Place, Paid by Linear Foot	LF	12		
32 10 00c	Detectable Warning Surface, Installed in Concrete Sidewalk Ramp	EA	3		
32 92 19	Seeding				
32 92 19a	Temporary Seeding	LF	600		
32 92 19b	Permanent Seeding	LF	600		
33 40 00	Storm Sewerage				
33 40 00a	18-inch RCP Storm Drain Pipe, Including Excavation, Stone Bedding, Pipe Installation, Backfill, Complete-In-Place.	LF	48		
33 40 00b	18-Inch Corrugated Plastic (CPP) Storm Drain Pipe, Including Excavation, Stone Bedding, Pipe Installation, Backfill, Complete-In-Place.	LF	300		
33 40 00c	18-Inch CMP/ Slotted Drain Pipe, Including Excavation, Demo of Old Pipe/Structures, Stone Bedding, Pipe Installation, Backfill, Complete-In-Place.	LF	100		
33 40 00d	Pre-Cast Flared End Section for 18-Inch RCP, Including Excavation, Stone Bedding, Backfill, Complete-In-Place	EA	3		

Item No.	Description	Unit	Est. No. of Units	Unit Price	Item Total
33 40 00e	Junction Box , Including Excavation, Stone Bedding, Pipe Connections, Backfill, Concrete top, Complete-In-Place	EA	1		
TOTAL SCHEDULE 1 (STATION 39+50 TO 33+00 DRAWING 11.2)				\$	
SCHEDULE 2 - STATION 33+00 TO STATION 22+00 (DRAWING NO.10.1)					
01 22 00	Mobilization and Performance Bond (Max 4.5% of Bid), Including Elevation Control, Site Layout, Utility Location, and Construction Staking	LS	1		
01 22 00b	Traffic Control Devices to Meet MUTCD and GDOT Requirements	LS	1		
03 30 00	Cast-In-Place Concrete, Includes All Materials and Labor				
03 30 00a	Class B (3,000 psi) Concrete for Utility Crossings , Including Excavation, Bedding, and Backfill in Areas Shown on the Plans and as directed by the Engineer	CY	5		
03 30 40	Concrete Sidewalks and Driveways, Includes All Materials and Labor				
03 30 40a	4-Inch-Thick Concrete for Sidewalk , Class A (4,000 psi), Including Excavation, Grading, Subgrade Preparation with up to 4-inches of Base Stone, Concrete Poured and Finished, Ramps, Joints, etc., Complete-in-Place	LF	950		
03 30 40b	Concrete Sidewalk with Turned Down Header Curb (Less than 30" Tall) at Front or Back of Sidewalk , Class A (4,000 psi), Including Saw Cutting, Excavation, Form Work, Pouring and Finishing Concrete Curb, Expansion Joints, Caulking, and Parking Lot Repair, Complete in Place	LF	150		
03 30 40c	Concrete Sidewalk with Turned Up Header Curb at Back of Sidewalk , Class A (4,000 psi), Including Saw Cutting, Excavation, Form Work, Pouring and Finishing Concrete Curb, Expansion Joints, Caulking, and Parking Lot Repair, Complete in Place	LF	40		
03 30 50	Concrete Curb, Gutter, or Combined Curb and Gutter				
03 30 50a	Concrete Header Curb , Class A (4,000 psi), Including Saw Cutting, Excavation, Stone Bedding, Form Work, Pouring and Finishing Concrete Curb, Expansion Joints, Caulking, and Roadway Repair, Complete in Place	LF	10		
03 30 50b	Concrete Curb and Gutter , Class A (4,000 psi), Including Saw Cutting, Excavation, Form Work, Pouring and Finishing Concrete, Expansion Joints, Caulking, and Asphalt Repair, Complete in Place	LF	70		
	Signage				
636-1	R1-1 Stop Sign	EA	1		
636-2	R1-6a Stop for Pedestrians Sign	EA	3		
636-3	Remove and Relocate Stop Sign, Warning Sign, or Street Sign	EA	1		

Item No.	Description	Unit	Est. No. of Units	Unit Price	Item Total
31 20 00	Earthwork				
31 20 00a	Unclassified Demolition/Excavation. Unclassified Demolition/Excavation of Existing Roadway, Curbs, Sidewalks, Brick and Debris Required to Fully Prepare the Sidewalk Subgrade; Including Saw-Cutting, Removal and Disposal of Spoil, Cuts and Fills Where Necessary, Ditch Grading, and Re-Setting Valve Covers, and Meter Boxes	LS	1		
31 20 00b	Crushed Rock Bedding Material in Excess of Standard Bedding or Leveling, Not Paid in Concrete Items Where Unsuitable Soil is Encountered or Where Additional Material for Bedding or Grading is Required or as Directed by the Engineer, Including Undercut Excavation, Disposal, and Stone Placement	TN	30		
31 25 00	Slope Protection and Erosion Control				
31 25 00a	Compost Filter Sock, Including Installation of Posts and Removal After Site Stability	LF	200		
31 25 00b	Rip Rap Stone, Complete-in-Place Where Shown on Plans for Ditch Construction, Outlet Protection, Slope Protection, Check Dams, and as Directed by the Engineer. Including Excavation, Filter Fabric Installation and Stone Placement, Complete in Place	TN	20		
31 25 00c	Straw Matting for Slope or Ditch Stabilization, Including Staples, as Shown on the Plans or as directed by the Engineer or Owner	SY	800		
31 25 00d	Concrete Washout Structure	EA	1		
32 10 00	Paving and Striping				
32 10 00a	Thermoplastic Cross Walk Striping, Including 5-Inch White Traffic Stripe per GDOT Standard T-11A, Complete in Place, Paid by Linear Foot Station to Station Across Drives and Roads	LF	268		
32 10 00b	Thermoplastic Solid Stripe for Stop Bar, Including 24-Inch White Traffic Stripe per GDOT Standard, Complete in Place, Paid by Linear Foot	LF	16		
32 10 00c	Detectable Warning Surface, Installed in Concrete Sidewalk Ramp	EA	10		
32 92 19	Seeding				
32 92 19a	Temporary Seeding	LF	800		
32 92 19b	Permanent Seeding	LF	800		
32 92 31	Permanent Stabilization, Landscape Mulch, 2-inch thick, Hard Wood, natural color, Complete-in-place in planter areas	CF	30		
33 40 00	Storm Sewerage				
33 40 00a	15-inch RCP Storm Drain Pipe, Including Excavation, Stone Bedding, pipe Installation, Backfill, Complete-In-Place.	LF	48		
33 40 00b	Pre-Cast Flared End Section for 15-Inch RCP, Including Excavation, Stone Bedding, Backfill, Complete in Place	EA	2		

Item No.	Description	Unit	Est. No. of Units	Unit Price	Item Total
33 40 00c	Storm Drain Inlet/Catch Basin (Box Type on GDOT Standard Drawing 1035) , Including Excavation, Stone Bedding, Structure, Frame and Grate, Backfill, Complete-In-Place.	EA	3		
TOTAL SCHEDULE 2 (STATION 33+00 TO 22+00 DRAWING 10.1)				\$	
SCHEDULE 3 - STATION 22+00 TO STATION 11+00 (DRAWING NO. 9.1)					
01 22 00	Mobilization and Performance Bond (Max 4.5% of Bid), Including Elevation Control, Site Layout, Utility Location, and Construction Staking	LS	1		
01 22 00b	Traffic Control Devices to Meet MUTCD and GDOT Requirements	LS	1		
03 30 00	Cast-In-Place Concrete, Includes All Materials and Labor				
03 30 00a	Class B (3,000 psi) Concrete for Utility Crossings , Including Excavation, Bedding, and Backfill in Areas Shown on the Plans and as directed by the Engineer	CY	5		
03 30 40	Concrete Sidewalks and Driveways, Includes All Materials and Labor				
03 30 40a	4-Inch-Thick Concrete for Sidewalk , Class A (4,000 psi), Including Excavation, Grading, Subgrade Preparation with up to 4-inches of Base Stone, Concrete Poured and Finished, Ramps, Joints, etc., Complete-in-Place	LF	775		
03 30 40b	Concrete Sidewalk with Turned Down Header Curb (Less than 30" Tall) at Front or Back of Sidewalk , Class A (4,000 psi), Including Saw Cutting, Excavation, Form Work, Pouring and Finishing Concrete Curb, Expansion Joints, Caulking, and Parking Lot Repair, Complete in Place	LF	150		
03 30 40c	Concrete Sidewalk with Turned Up Header Curb at Back of Sidewalk , Class A (4,000 psi), Including Saw Cutting, Excavation, Form Work, Pouring and Finishing Concrete Curb, Expansion Joints, Caulking, and Parking Lot Repair, Complete in Place	LF	175		
03 30 40d	6-Inch-Thick Concrete for Driveway Aprons , Class A (4,000 psi), Including Excavation, Grading, Subgrade Preparation with minimum 4 Inches of Stone Base, Reinforcement, Concrete Poured and Finished, and Spoil Dirt Disposal, etc., Complete-in-Place	SF	240		
03 30 50	Concrete Curb, Gutter, or Combined Curb and Gutter				
03 30 50a	Concrete Header Curb , Class A (4,000 psi), Including Saw Cutting, Excavation, Stone Bedding, Form Work, Pouring and Finishing Concrete Curb, Expansion Joints, Caulking, and Roadway Repair, Complete in Place	LF	10		
03 30 50b	6" x 6" Concrete Formed Curb , Class A (4,000 psi), Including Form Work, Dowel Installation, Pouring and Finishing Concrete Curb, Complete in Place (Approximate Station 13+70 to 14+80)	LF	110		
03 30 50c	Concrete Curb and Gutter , Class A (4,000 psi), Including Saw Cutting, Excavation, Form Work, Pouring and Finishing Concrete, Expansion Joints, Caulking, and Asphalt Repair, Complete in Place	LF	20		

Item No.	Description	Unit	Est. No. of Units	Unit Price	Item Total
Signage					
636-1	R1-1 Stop Sign	EA	1		
636-2	Remove and Relocate Stop Sign, Warning Sign, or Street Sign	EA	1		
31 20 00 Earthwork					
31 20 00a	Unclassified Demolition/Excavation. Unclassified Demolition/Excavation of Existing Roadway, Curbs, Sidewalks, Brick and Debris Required to Fully Prepare the Sidewalk Subgrade; Including Saw-Cutting, Removal and Disposal of Spoil, Cuts and Fills Where Necessary, Ditch Grading, and Re-Setting Valve Covers, and Meter Boxes	LS	1		
31 20 00b	Crushed Rock Bedding Material in Excess of Standard Bedding or Leveling, Not Paid in Concrete Items Where Unsuitable Soil is Encountered or Where Additional Material for Bedding or Grading is Required or as Directed by the Engineer, Including Undercut Excavation, Disposal, and Stone Placement	TN	20		
31 25 00 Slope Protection and Erosion Control					
31 25 00a	Compost Filter Sock, Including Installation of Posts and Removal After Site Stability	LF	200		
31 25 00b	Rip Rap Stone, Complete-in-Place Where Shown on Plans for Ditch Construction, Outlet Protection, Slope Protection, Check Dams, and as Directed by the Engineer. Including Excavation, Filter Fabric Installation and Stone Placement, Complete in Place	TN	25		
31 25 00c	Straw Matting for Slope or Ditch Stabilization, Including Staples, as Shown on the Plans or as directed by the Engineer or Owner	SY	800		
31 25 00d	Concrete Washout Structure	EA	1		
32 10 00 Paving					
32 10 00a	Thermoplastic Cross Walk Striping, Including 5-Inch White Traffic Stripe per GDOT Standard T-11A, Complete in Place, Paid by Linear Foot Station to Station Across Drives and Roads	LF	140		
32 10 00b	Thermoplastic Solid Stripe for Stop Bar, Including 24-Inch White Traffic Stripe per GDOT Standard, Complete in Place, Paid by Linear Foot	LF	12		
32 10 00c	Detectable Warning Surface, Installed in Concrete Sidewalk Ramp	EA	6		
32 92 19 Seeding					
32 92 19a	Temporary Seeding	LF	850		
32 92 19b	Permanent Seeding	LF	850		
32 92 31	Permanent Stabilization, Landscape Mulch, 2-inch thick, Hard Wood, natural color, Complete-in-place in planter areas	CF	30		
33 40 00 Storm Sewerage					
33 40 00a	15-inch RCP Storm Drain Pipe, Including Excavation, Stone Bedding, pipe Installation, Backfill, Complete-In-Place.	LF	24		

Item No.	Description	Unit	Est. No. of Units	Unit Price	Item Total
33 40 00b	Pre-Cast Flared End Section for 15-Inch RCP , Including Excavation, Stone Bedding, Backfill, Complete in Place	EA	4		
TOTAL SCHEDULE 3 (STATION 22+00 TO 11+00 DRAWING 9.1)				\$	
SCHEDULE 4 - STATION 11+00 TO STATION 0+00 (DRAWING NO. 8.1)					
01 22 00	Mobilization and Performance Bond (Max 4.5% of Bid), Including Elevation Control, Site Layout, Utility Location, and Construction Staking	LS	1		
01 22 00b	Traffic Control Devices to Meet MUTCD and GDOT Requirements	LS	1		
03 30 00	Cast-In-Place Concrete, Includes All Materials and Labor				
03 30 00a	Class B (3,000 psi) Concrete for Utility Crossings , Including Excavation, Bedding, and Backfill in Areas Shown on the Plans and as directed by the Engineer	CY	5		
03 30 40	Concrete Sidewalks and Driveways, Includes All Materials and Labor				
03 30 40a	4-Inch-Thick Concrete for Sidewalk , Class A (4,000 psi), Including Excavation, Grading, Subgrade Preparation with up to 4-inches of Base Stone, Concrete Poured and Finished, Ramps, Joints, etc., Complete-in-Place	LF	370		
03 30 40b	Concrete Sidewalk with Turned Down Header Curb (Less than 30" Tall) at Front or Back of Sidewalk , Class A (4,000 psi), Including Saw Cutting, Excavation, Form Work, Pouring and Finishing Concrete Curb, Expansion Joints, Caulking, and Parking Lot Repair, Complete in Place	LF	730		
03 30 40c	Concrete Sidewalk with Turned Up Header Curb at Back of Sidewalk , Class A (4,000 psi), Including Saw Cutting, Excavation, Form Work, Pouring and Finishing Concrete Curb, Expansion Joints, Caulking, and Parking Lot Repair, Complete in Place	LF	40		
03 30 50	Concrete Curb, Gutter, or Combined Curb and Gutter				
03 30 50a	Concrete Header Curb , Class A (4,000 psi), Including Saw Cutting, Excavation, Stone Bedding, Form Work, Pouring and Finishing Concrete Curb, Expansion Joints, Caulking, and Roadway Repair, Complete in Place	LF	20		
03 30 50b	Concrete Curb and Gutter , Class A (4,000 psi), Including Saw Cutting, Excavation, Form Work, Pouring and Finishing Concrete, Expansion Joints, Caulking, and Asphalt Repair, Complete in Place	LF	40		
	Signage				
636-1	R1-1 Stop Sign	EA	3		
636-2	Remove and Relocate Stop Sign, Warning Sign, or Street Sign	EA	1		

Item No.	Description	Unit	Est. No. of Units	Unit Price	Item Total
31 20 00	Earthwork				
31 20 00a	Unclassified Demolition/Excavation. Unclassified Demolition/Excavation of Existing Roadway, Curbs, Sidewalks, Brick and Debris Required to Fully Prepare the Sidewalk Subgrade; Including Saw-Cutting, Removal and Disposal of Spoil, Cuts and Fills Where Necessary, Ditch Grading, and Re-Setting Valve Covers, and Meter Boxes	LS	1		
31 20 00b	Crushed Rock Bedding Material in Excess of Standard Bedding or Leveling, Not Paid in Concrete Items Where Unsuitable Soil is Encountered or Where Additional Material for Bedding or Grading is Required or as Directed by the Engineer, Including Undercut Excavation, Disposal, and Stone Placement	TN	20		
31 25 00	Slope Protection and Erosion Control				
31 25 00a	Compost Filter Sock, Including Installation of Posts and Removal After Site Stability	LF	200		
31 25 00b	Rip Rap Stone, Complete-in-Place Where Shown on Plans for Ditch Construction, Outlet Protection, Slope Protection, Check Dams, and as Directed by the Engineer. Including Excavation, Filter Fabric Installation and Stone Placement, Complete in Place	TN	20		
31 25 00c	Straw Matting for Slope or Ditch Stabilization, Including Staples, as Shown on the Plans or as directed by the Engineer or Owner	SY	800		
31 25 00d	Concrete Washout Structure	EA	1		
32 10 00	Paving				
32 10 00a	Asphalt Pavement Replacement for Driveways, Parking Lots, and Streets, Trench Width Repair 4-inches Thick with 2.5-inches of 12.5 mm and 1.5-inches of 9.5 mm GDOT Mix, Including Saw-cutting, Excavation, Compacted Base Stone, Bituminous Tack/Prime Coat(s), and Asphalt Placement	TN	10		
32 10 00b	Thermoplastic Cross Walk Striping, Including 5-Inch White Traffic Stripe per GDOT Standard T-11A, Complete in Place, Paid by Linear Foot Station to Station Across Drives and Roads	LF	116		
32 10 00c	Thermoplastic Solid Stripe for Stop Bar, Including 24-Inch White Traffic Stripe per GDOT Standard, Complete in Place, Paid by Linear Foot	LF	48		
32 10 00d	Detectable Warning Surface, Installed in Concrete Sidewalk Ramp	EA	9		
32 92 19	Seeding				
32 92 19a	Temporary Seeding	LF	900		
32 92 19b	Permanent Seeding	LF	900		
32 92 31	Permanent Stabilization, Landscape Mulch, 2-inch thick, Hard Wood, natural color, Complete-in-place in planter areas	CF	30		

Item No.	Description	Unit	Est. No. of Units	Unit Price	Item Total
33 40 00	Storm Sewerage				
33 40 00a	12-Inch RCP Storm Drain Pipe , Including Excavation, Stone Bedding, Pipe Installation, Backfill, Complete-In-Place.	LF	20		
33 40 00b	18-inch RCP Storm Drain Pipe , Including Excavation, Stone Bedding, Backfill, Complete-In-Place.	LF	32		
33 40 00c	Pre-Cast Flared End Section for 12-Inch RCP , Including Excavation, Stone Bedding, Backfill, Complete in Place	EA	1		
33 40 00d	Pre-Cast Flared End Section for 18-Inch RCP , Including Excavation, Stone Bedding, Backfill, Complete in Place	EA	1		
33 40 00e	Storm Drain Inlet/Catch Basin (Box Type on GDOT Standard Drawing 1035) , Including Excavation, Stone Bedding, Structure, Frame and Grate, Backfill, Complete-In-Place.	EA	1		
33 40 00f	Elbow Type Storm Drain Inlet (GDOT Standard Drawing 1035) , Including Excavation, Stone Bedding, 12-inch Minimum Elbow Installation, Backfill, Complete-In-Place.	EA	1		
TOTAL SCHEDULE 4 (STATION 11+00 TO 0+00 DRAWING 8.1)				\$	
SUMMARY					
TOTAL SCHEDULE 1 (STATION 39+50 TO 33+00 DRAWING 11.2)				\$	
TOTAL SCHEDULE 2 (STATION 33+00 TO 22+00 DRAWING 10.1)				\$	
TOTAL SCHEDULE 3 (STATION 22+00 TO 11+00 DRAWING 9.1)				\$	
TOTAL SCHEDULE 4 (STATION 11+00 TO 0+00 DRAWING 8.1)				\$	
TOTAL BID (ALL SCHEDULES)				\$	
BIDDER					
				DATE	
BY		(Signature)		TITLE	
ADDRESS					
CITY		STATE		ZIP	
TELEPHONE				E-MAIL	