

LETTER OF TRANSMITTAL

TO:

Integrated Builds
 KTM Builders
 Tyson & Assoc. Construction Company, Inc.
 Astra Group, LLC
 Baseline Sports Construction

Jon Clinard jclinard@integratedbuilds.com
 Miles Knox milesk@ktmbuildersllc.com
 Kurt Teasley kurt@tysoncon.com
 Graham Nelson gnelson@astragroupinc.com
 Gayla gaylal@baselinellc.com

City of Ringgold

Mark Vaughn citymanager@cityofringgoldga.gov

Deltek, Inc.
 The Blue Book
 Dodge Data & Analytics
 Associated General Contractors
 Builders Exchange of Tennessee
 Construct Connect

Patricia Manarin publicrecords@deltek.com
 Erin McVeigh emcveigh@mail.thebluebook.com
dodge.bidding@construction.com
planroom@agcetn.org
 Heather Lowery heather@bxtn.org
 Rachael Taylor rachael.taylor@constructconnect.com

FROM: Philip Schofield, P.E., Senior Project Manager

DATE: June 26, 2023

PROJ. NO.: G22005-05
SUBJECT: Addendum No. 3
 Recreational Complex Phase I
 City of Ringgold, Georgia

PAGES: 2 pages follow

| | |
|---|---|
| <p>PLEASE RESPOND</p> <p>→ → → →</p> | <p>TO CONFIRM RECEIPT OF THIS ADDENDUM NO. 3 PLEASE SIGN AND EMAIL TO CTI</p> <p>vvisco@ctiengr.com</p> <p>Company _____</p> <p>Signature _____</p> <p>Title _____</p> <p>Date _____</p> |
|---|---|

ADDENDUM NO. 3

**RECREATIONAL COMPLEX PHASE I
CITY OF RINGGOLD, GEORGIA**

The following changes to the Contract Documents:

I. CONTRACT DOCUMENTS

- A. **Section 00 42 00, Bid Schedule:** DELETE 00 42 00-2.2 and REPLACE with the attached page 00 42 00-2.3.

Date: June 26, 2023

CTI Engineers, Inc.
/s/ Philip R. Schofield, P.E.
Senior Project Manager

| Item No. | Description | Unit | Est. No. of Units | Unit Price | Item Total |
|---|--|------|-------------------|-------------|-------------|
| 32 92 19e | Rain Garden Landscape Allowance | LS | 1 | \$ 5,000.00 | \$ 5,000.00 |
| 33 40 00 | Storm Sewerage | | | | |
| 33 40 00a | 36-inch Diameter Reinforced Concrete Pipe (RCP) , Including Excavation, Stone Bedding, Stone Backfill, and Disposal of Soil and Debris; Complete-in-Place. | LF | 128 | | |
| 33 40 00b | Inlet Structure , Including Excavation, Stone Bedding, Stone Backfill, and Disposal of Soil and Debris; Complete-in-Place. | EACH | 2 | | |
| 33 40 00c | 18-inch Diameter Reinforced Concrete Pipe (RCP) , Including Excavation, Stone Bedding, Stone Backfill, and Disposal of Soil and Debris; Complete-in-Place. | LF | 56 | | |
| 33 40 00d | Built-in-Place Natural Mountain Stone Headwall , Including Excavation, Stone Bedding, Concrete Foundation, Stone Placement, Grout, Stone Cap, Backfill and site restoration, Complete-in-Place | EACH | 2 | | |
| 34 00 00 | Signs and Striping | | | | |
| 34 00 00a | Standard 5-Inch White Solid Traffic Stripe for Parking Lot Spots. | LF | 1,500 | | |
| 34 00 00b | White (Thermoplastic) Type 1 Turn Arrow for Roads per GDOT Standard Drawing T-12B. | EACH | 2 | | |
| 34 00 00c | Handicapped Pavement Markings (Thermoplastic) , Including White on Blue Painted Symbol, 2 Spaces Complete, 5" Yellow Paint Lines and Cross Hatch, etc. | EACH | 2 | | |
| 34 00 00d | MUTCD Handicap Parking Signs , Including Posts and all Hardware, Complete-in-Place. | EACH | 4 | | |
| 34 00 00e | Pre-cast Concrete Wheel Stops | EACH | 45 | | |
| SCHEDULE I - TOTAL BASE BID: \$ | | | | | |
| SCHEDULE IIA: ALTERNATE 1 - ASPHALT BASKETBALL AND PICKLEBALL COURTS | | | | | |
| 34 00 00 | Asphalt Basketball and Pickleball Courts | | | | |
| 34 00 00a | 2" Compacted Crushed Base Stone for Basketball and Pickleball Courts , Including Stone Placement, Compaction, and Fine Grading. | LS | 1 | | |
| 34 00 00b | 10 Pickleball Courts , Including Asphalt (2.5" binder + 1" Topping), Nets and Poles. Complete-In-Place. | LS | 1 | | |
| 34 00 00c | Pickleball Coating System , Flexible, Acrylic, Textured, Base Color Coating System. | LS | 1 | | |
| 34 00 00d | Basketball Courts , Including Asphalt, Striping and Paint. Complete-In-Place. | LS | 1 | | |
| 34 00 00e | Basketball Coating System , Flexible, Acrylic, Textured, Base Color Coating System. | LS | 1 | | |
| 35 00 00f | First Team Tyrant Fixed Height Basketball System (or equivalent) . Backboard to be Steel 36"x60", pole diameter to be not less than 6", Post Foundations to be not less than 24" in diameter and not less than 50" in depth. Complete-in-Place. | EACH | 2 | | |
| 34 00 00g | 4' Tall Vinyl Coated Chain Link Fence for Pickleball Courts , Including Fence Post, Fence Material, and Installation. Complete-In-Place. | LF | 900 | | |
| 35 00 00h | Fence Access Gate , Including Fence Post, Fence Gate, and Installation. Complete-In-Place. | EACH | 4 | | |
| TOTAL SCHEDULE IIA: ALTERNATE 1 - ASPHALT BASKETBALL AND PICKLEBALL COURTS: \$ | | | | | |
| SCHEDULE IIB: ALTERNATE 2 - CONCRETE BASKETBALL AND PICKLEBALL COURTS | | | | | |
| 34 00 00 | Concrete Basketball and Pickleball Courts | | | | |
| 34 00 00a | 6" Compacted GAB for Basketball and Pickleball Courts | LS | 1 | | |
| 34 00 00b | 10 Pickleball Courts , Including Class A Concrete, WWF6x6x1.4/1.4, Expansion Joints, Nets and Poles, Complete-In-Place. | LS | 1 | | |
| 34 00 00c | Pickleball Coating System , Flexible, Acrylic, Textured, Base Color Coating System for all 10 Courts. | LS | 1 | | |
| 34 00 00d | Basketball Court Concrete , Including 6" Thick Class A Concrete, WWF6x6x1.4/1.4, Expansion Joints, etc. Complete-In-Place. | LS | 1 | | |